

**ESTL** Overview

Name:


Mario Delgado

Date:


Page:

Sept. 2002


1



# **ESTL TEST CONCEPT**



All communications scenarios pictured as well as MCC data processing can be emulated in the ESTL test bed



# What does ESTL consist of?


Name:		
	Mario Delgado	

Date: Page: Sept. 2002


#### Hardware/Software

- ? ESTL facility represents a \$150 million capital equipment investment containing 18,500 square feet of active floor space
- ? As an end-to-end testbed the ESTL contains high-fidelity equipment of both ground and spacecraft communications systems
- ? Significant features of the ESTL include the following:
  - ? Five RF shielded enclosures for spacecraft testing
  - ? High fidelity equipment of both types of ground stations
    - GSTDN direct link ground station,
    - TDRS Ground Terminal
  - ? A TDRS satellite communication system with S-band single access (SSA) and Ku-band single access (KSA) capability
  - ? Unique test instrumentation systems, including Dynamic Doppler Frequency profiles and accurate, controlled, dynamic space loss emulation
  - ? Space Shuttle Orbiter Ku-band, S-band, and ultrahigh frequency (UHF) prototype and/or qualification units (including encryption equipment)
  - ? GFE products such as SSCS, OIU, ECOMM
  - ? A roof mounted, 16-foot S-band antenna system
  - ? Three antenna radomes for RF transmission/reception from on orbit spacecraft or TDRS's

# ESTL/TDRSS INTERFACE TEST CONFIGURATION



ESTL transmits to TDRSS network for Shuttle/Station/GFE/payload mission pre-flight checkouts/tests and hardware, firmware, and software modification checkouts for MCC and STGT



# ESTL Services to the Agency

Name:		
	Mario Delgado	
1		<b>D</b>

Date:


Page:

Sept. 2002

5

### **ESTL Products:** we provide

- ? In depth RF communications performance verification and characterization testing for all Human Spaceflight Programs
- ? In depth RF characterization testing for payloads, satellites, and other unmanned vehicles
- ? Shuttle and Station RF Anomaly Resolution Test Bed Pre-launch, Real-time and Post-flight
- ? Support to TDRSS Network Shuttle Pre-launch Verification/Validation Tests, TDRS checkout, TDRSS Network Firmware checkouts
- ? Avionics GFE development and verification testing
- ? Venue for future R&D communications ventures
- ? RF Communication Certification
- ? MCC Ground Support



# **ESTL Products**

Name:	
	Mario Delgado

Date:


Page:

Sept. 2002

6

## ESTL provides complete life cycle test capability for all programs.

- ? Analysis model verification
- ? Design Development (e.g. OCA, HDTV)
- ? System Verification (Shuttle & Station S-band, Ku-band, UHF)
- ? System Certification (ECOMM, SSCS)
- ? System preflight checkout (Hubble Space Telescope)
- ? On-Orbit support (FM System TV downlink first orbit)
- ? On-Orbit anomaly investigation/resolution
- ? Sustaining engineering of operational systems



Su	bi	e	ct

# **ESTL** Personnel


Name:		
	Mario Delg	gado
Date:		Page:

Date:

Sept. 2002

### **Experience**

- ? Highly trained and experienced test team in place with over 39 years of corporate knowledge in RF **Communication Systems Testing**
- ? Complex, specialized test techniques developed and continuously refined over the life of the facility
- ? Specialized test equipment developed in-house to support unique test needs
- ? ESTL ground station support personnel (Honeywell) provided by operational ground station support contractor also with 39 years experience supporting manned programs
- ? ESTL test personnel highly familiar with mission operations (Ground Network and MOD)
- ? ESTL personnel highly familiar with Shuttle and Station communication systems
- ? Personnel are cross-trained and have more than one function in the ESTL.



# ESTL Equipment

Name:		
	Mario Delgado	

Date:

Page:

Sept. 2002


8

## **Space Shuttle Orbiter**

- ? Ku-band
  - ?EA1
  - ? Signal Processor
  - ? Ku-band Deployed Assembly System (antenna)
- ? S-band
  - ? **PA**
  - ?NSP
  - ? Transponder
  - ? Antenna Switch Assembly
  - ? Preamp
  - ? ATU
  - ? ACCU
  - ? FM Transmitter
  - ? FM signal processor
- ? Other
  - ?OIU
  - ?SSOR

# **International Space Station**

- ? Test Bed can accept DVTM or Flight Units
- ? Space to Ground System (SGS) Antenna (proto-flight spare)
- ? SSSR



ESTL Equipment (cont.)

Name:	
	Mario Delgado
	I

Sept. 2002

9

Page:


#### **Ground Stations**

- ? Second TDRS Ground Station (exact copy)
- ? Ground Tracking Data Network (exact copy)

**TDRS Satellite Simulator (electrically equivalent)** 

# **Ground Processing Equipment**

- ? Front End Processor (station and shuttle)
- ? GSTDN ground processing hardware (MBR)



ESTL Equipment (cont.)

Name:

Mario Delgado

Date:

Page:


Sept. 2002


10











# ESTL Special Test Equipment

Name:	
	Mario Delgado

Date:

Sept. 2002

11

Page:

#### Calibrated hard-line RF Paths for S-band, Ku-band, and UHF

- ? 5 Shielded Enclosures
- ? Calibrated continuously-variable Attenuators; DC-4GHz, 12-18GHz

#### Antennae

- ? Three antenna radomes for RF transmission/reception from on orbit spacecraft or TDRS's
- ? Roof mounted, 16-foot S-band antenna system

## **Bit and Frame Error Equipment**


- ? High Rate Open and Closed Loop Bit Error Detectors, DC to 100Mbps
- ? Open Loop Bit Error Detectors to 700Mbps
- ? Frame Sync Status Detectors

### Interfaces to MCC, SAIL, ISIL

- ? EHROCS (fiber equipment)
- ? Analog Voice
- ? SDI

### Support

- ? ESTL Display system
- ? Electronic Monitoring Alarm System (e.g., over-temp, over-voltage)
- ? ISS Data Handling System (BSP Simulator, control station boxes)



# ESTL External Interfaces

Name:


Mario Delgado

Date:

Page:

Sept. 2002

12





# Commercial Usage of ESTL

Name:		
	Mario Delgado	
Date:		Page:

Date:

Sept. 2002

13

External customers use the Space Act Agreement vehicle to work with ESTL

## **External Space Shuttle Customers**


- ? European Space Agency
- ? Russian Space Agency.

## **External Space Station Customers**

- ? European Space Agency
- ? Naval Research Laboratory

### **Other Customers**

- ? Provided testbed and additional expertise for Spacehab to develop a telemetry link multiplex interface with the Shuttle Ku-band Signal Processor (Ku-SP), Space Network, and Mission Control Center
- ? Discussing tests for Spacehab related to compatibility with Inmarsat



# New ESTL Shuttle Upgrades

Name:
Mario Delgado

Date:

Page:

Sept. 2002

14

## **Digital Operational Recorder**

? Nonflight unit to replace the engineering unit used by ESTL

### Solid State Recorder (Mass Memory Unit (MMU))


- ? Replacement for the Operational Recorder
- ? Only plays back in forward direction
- ? Has playback rates (2048, 1024, 960, 192, 128, & 60 kbps)
- ? ESTL developed and ATP'd a controller that operates thru the MDM port

# **Space-to-Space Communications System (SSCS)**

- ? Replacement for EVA backpack
- ? ESTL maintains an SSOR, SSSR, and SSER (can accommodate 2 more SSER units)
- ? Currently developing a monitoring system to display the status of the radio network

#### **DTV MUX/DEMUX**

- ? Integrated a flight DTV MUX and a GSE DEMUX into the ESTL testbed
- ? SDI tie lines were installed this year that allow for signal interface with MCC DTV GSE



# ESTL Testbed Upgrades

Name:
Mario Delgado

Date:

Page:

Sept. 2002

15

## **ESTL High Rate Optical Communications System (EHROCS)**

- ? Capable of supporting up to 100 Mbps (>10 of operation)
- ? Currently developing >1 Gbps fiber network for future Ka-Band support

### **Small Conversion Device (SCD)**

- ? Provides an interface to the IONET which allows access to the NASCOM community
- ? Up to 3 Mbps of offsite capability

### **Clock and Data Recovery System**


- ? Bit sync for the TSI FEP
- ? Supports I/Q downlink of up to 600 Mb per channel

#### **TSI Front End Processor (FEP)**

- ? Currently only Record/Playback Implemented
- ? Upgradeable to full FEP processing capability
- ? 600 Mbps capability (can support 75 Mbps and 150 Mbps station downlinks)
- ? 300 GB Redundant Array of Independent Disks (RAID) for recording

#### **Loral Front End Processor (FEP)**

- ? Second unit due to arrive in early 2003 for STS processing
- ? Operates up to 50 Mbps
- ? Current FEP has a full compliment of station cards
  - ? 12 TAXI I/O cards (Fiber, ~50 Mbps, 8 payload channels/4 video channels)
  - ?3 TIO cards (RS422, <10 Mbps, 2 inputs/2 outputs)
  - ? 1 HR TIO card (Fiber/ECL, 50 Mbps, 1 input/1 output)
  - ? 2 DSP mezzanine cards (to support station audio and Reed-Solomon)



# ESTL Testbed Upgrades (cont.)

Name:		
	Mario Delgado	

Date:

Page:

Sept. 2002


16

#### **TSI Video Converter**

- ? 4 video converter channels
- ? Each channel converts CCSDS VBSP packets to NTSC video

### **ESTL TAXI Test Set (HRFM Test Set)**

- ? 12 TX/12 RX independent channels
- ? Each channel operates up to 100 Mbps
- ? Recover/Record 90 GB
- ? Bitstream mode
  - ? Generate serial continuous data stream
    - Custom frame formats (constant, dynamic)
    - File playback of real data
    - Variable parsing schemes
    - Insert errors, illegal delimiter/TAXI codes, vary the clock frequency
  - ? Recover/Record serial data
    - Real time checks
    - Post recovery analysis (bit for bit, byte for byte, frame for frame)
- ? CCSDS Packet mode
  - ? Generate packet streams
    - Custom frame formats (constant/variable length)
    - File playback of real data
    - Insert errors, illegal TAXI codes, illegal lengths, vary the clock frequency
    - Variable parsing schemes
  - ? Recover/Record serial data
    - Real time checks
    - Post recovery analysis (bit for bit, byte for byte, packet for packet)



Su	bi	ie	ct
Uu	~J	<b>,</b>	UL

**ESTL Contact** 

Name: Mario Delgado Page:

Date:

Sept. 2002

17

# **ESTL Facility Manager**

Ned J. Robinson III EV4/System Analysis & Test Branch ned.j.robinson1@jsc.nasa.gov 281-483-0130